

TRANSMITTAL LETTER TO THE UNITED STATES

145-3065-U

DESIGNATED/ELECTED OFFICE (DO/EO/US)

U.S. APPLICATION NO. (IF KNOWN, SEE 37 CFR

CONCERNING A FILING UNDER 35 U.S.C. 371

10/088700

INTERNATIONAL APPLICATION NO.
PCT/EP00/07353

INTERNATIONAL FILING DATE
July 29, 2000

PRIORITY DATE CLAIMED
September 21, 1999

TITLE OF INVENTION

AUTOMATIC VALVE FOR THE STABILIZATION OF A THERMOSTATIC MIXING DEVICE

APPLICANT(S) FOR DO/EO/US

Alfons Knapp

Applicant herewith submits to the United States Designated/Elected Office (DO/EO/US) the following items and other information:

1. ☒ This is a **FIRST** submission of items concerning a filing under 35 U.S.C. 371.
2. ☐ This is a **SECOND** or **SUBSEQUENT** submission of items concerning a filing under 35 U.S.C. 371.
3. ☒ This is an express request to begin national examination procedures (35 U.S.C. 371(f)). The submission must include items (5), (6), (9) and (24) indicated below.
4. ☒ The US has been elected by the expiration of 19 months from the priority date (Article 31).
5. ☒ A copy of the International Application as filed (35 U.S.C. 371 (c) (2))
 - a. ☒ is attached hereto (required only if not communicated by the International Bureau).
 - b. ☐ has been communicated by the International Bureau.
 - c. ☐ is not required, as the application was filed in the United States Receiving Office (RO/US).
6. ☐ An English language translation of the International Application as filed (35 U.S.C. 371(c)(2)).
 - a. ☐ is attached hereto.
 - b. ☐ has been previously submitted under 35 U.S.C. 154(d)(4).
7. ☒ Amendments to the claims of the International Application under PCT Article 19 (35 U.S.C. 371 (c)(3))
 - a. ☒ are attached hereto (required only if not communicated by the International Bureau).
 - b. ☒ have been communicated by the International Bureau.
 - c. ☐ have not been made; however, the time limit for making such amendments has NOT expired.
 - d. ☐ have not been made and will not be made.
8. ☐ An English language translation of the amendments to the claims under PCT Article 19 (35 U.S.C. 371(c)(3)).
9. ☒ An oath or declaration of the inventor(s) (35 U.S.C. 371 (c)(4)).
10. ☐ An English language translation of the annexes to the International Preliminary Examination Report under PCT Article 36 (35 U.S.C. 371 (c)(5)).
11. ☒ A copy of the International Preliminary Examination Report (PCT/IPEA/409).
12. ☒ A copy of the International Search Report (PCT/ISA/210).

Items 13 to 20 below concern document(s) or information included:

13. ☐ An Information Disclosure Statement under 37 CFR 1.97 and 1.98.
14. ☐ An assignment document for recording. A separate cover sheet in compliance with 37 CFR 3.28 and 3.31 is included.
15. ☐ A **FIRST** preliminary amendment.
16. ☐ A **SECOND** or **SUBSEQUENT** preliminary amendment.
17. ☐ A substitute specification.
18. ☒ A change of power of attorney and/or address letter.
19. ☐ A computer-readable form of the sequence listing in accordance with PCT Rule 13ter.2 and 35 U.S.C. 1.821 - 1.825.
20. ☐ A second copy of the published international application under 35 U.S.C. 154(d)(4).
21. ☐ A second copy of the English language translation of the international application under 35 U.S.C. 154(d)(4).
22. ☒ Certificate of Mailing by Express Mail
23. ☐ Other items or information:

U.S. APPLICATION NO. (IF KNOWN, SEE 37 CFR 1.101) 10/088700		INTERNATIONAL APPLICATION NO. PCT/EP00/07353		ATTORNEY'S DOCKET NUMBER 145-3065-U	
---	--	---	--	--	--

24. The following fees are submitted:

BASIC NATIONAL FEE (37 CFR 1.492 (a) (1) - (5)) :

<input checked="" type="checkbox"/> Neither international preliminary examination fee (37 CFR 1.482) nor international search fee (37 CFR 1.445(a)(2)) paid to USPTO and International Search Report not prepared by the EPO or JPO	\$1040.00	CALCULATIONS PTO USE ONLY	
<input type="checkbox"/> International preliminary examination fee (37 CFR 1.482) not paid to USPTO but International Search Report prepared by the EPO or JPO	\$890.00		
<input type="checkbox"/> International preliminary examination fee (37 CFR 1.482) not paid to USPTO but international search fee (37 CFR 1.445(a)(2)) paid to USPTO	\$740.00		
<input type="checkbox"/> International preliminary examination fee (37 CFR 1.482) paid to USPTO but all claims did not satisfy provisions of PCT Article 33(1)-(4)	\$710.00		
<input type="checkbox"/> International preliminary examination fee (37 CFR 1.482) paid to USPTO and all claims satisfied provisions of PCT Article 33(1)-(4)	\$100.00		
ENTER APPROPRIATE BASIC FEE AMOUNT =		\$1,040.00	

Surcharge of \$130.00 for furnishing the oath or declaration later than ☐ 20 ☐ 30 months from the earliest claimed priority date (37 CFR 1.492 (e)).

CLAIMS	NUMBER FILED	NUMBER EXTRA	RATE		
Total claims	17 - 20 =	0	x \$18.00		\$0.00
Independent claims	3 - 3 =	0	x \$84.00		\$0.00

Multiple Dependent Claims (check if applicable). ☒ \$280.00

TOTAL OF ABOVE CALCULATIONS = \$1,320.00

☐ Applicant claims small entity status. See 37 CFR 1.27. The fees indicated above are reduced by 1/2. \$0.00

SUBTOTAL = \$1,320.00

Processing fee of \$130.00 for furnishing the English translation later than ☐ 20 ☐ 30 months from the earliest claimed priority date (37 CFR 1.492 (f)). \$0.00

TOTAL NATIONAL FEE = \$1,320.00

Fee for recording the enclosed assignment (37 CFR 1.21(h)). The assignment must be accompanied by an appropriate cover sheet (37 CFR 3.28, 3.31) (check if applicable). ☐ \$0.00

TOTAL FEES ENCLOSED = \$1,320.00

	Amount to be refunded	\$
	charged	\$

a. ☐ A check in the amount of _____ to cover the above fees is enclosed.

b. ☒ Please charge my Deposit Account No. 13-1981 in the amount of \$1,320.00 to cover the above fees. A duplicate copy of this sheet is enclosed.


c. ☒ The Commissioner is hereby authorized to charge any additional fees which may be required, or credit any overpayment to Deposit Account No. 13-1981. A duplicate copy of this sheet is enclosed.

d. ☐ Fees are to be charged to a credit card. **WARNING:** Information on this form may become public. Credit card information should not be included on this form. Provide credit card information and authorization on PTO-2038.

NOTE: Where an appropriate time limit under 37 CFR 1.494 or 1.495 has not been met, a petition to revive (37 CFR 1.137(a) or (b)) must be filed and granted to restore the application to pending status.

SEND ALL CORRESPONDENCE TO:

Kwadjo Adusei-Poku
Masco Corporation
21001 Van Born Road
Taylor, Michigan 48180
(313) 792-6432


SIGNATURE

Kwadjo Adusei-Poku
NAME

39,892
REGISTRATION NUMBER

March 21, 2002
DATE

- 1 -

AUTOMATIC VALVE FOR THE STABILIZATION
OF A THERMOSTATIC MIXING DEVICE

TECHNICAL FIELD

This invention relates to an automatic valve intended for installation in the inlet of a thermostatic mixing device to stabilize its operation.

BACKGROUND OF THE DISCLOSURE

When a thermostatic mixing device, designed to be able to draw a certain flow rate, supplies an apparatus which, because of the high resistance that it creates against the flow, permits only the delivery of a much lesser flow rate, the pressure inside the thermostatic mixing device becomes close to the pressure in the water supply pipelines. If there develops, then, a considerable pressure difference between the hot water and the cold water supply pipelines, for example, due to the absorption of an apparatus with a high flow rate, such as a flowmeter flushing water device inserted on one of the pipelines due to the crosswise flow (the so-called cross-flow) that develops inside the thermostatic mixing device, the latter is in a state of instability or begins to oscillate with subsequent malfunctioning and instability of the temperature of the mixed water drawn by it.

This happens, for example, when a thermostatic mixing device, intended to supply in the absence of a strong resistance at the outlet a relatively high flow rate, such as, for example, 50 or 60 liters per minute at 3 bar, is used with a much lesser water delivery volume, for example, 9 liters per

- 2 -

minute, which is limited by the resistance offered to the flow by certain apparatuses. This case occurs, in particular, when the thermostatic mixing device is installed to supply a multiple shower stall, each of which is equipped with its own exclusion device, while the user employs only one shower. More generally, the same case occurs when the thermostatic mixing device is arranged to supply a plurality of apparatuses or only one or a few of them are actually in operation.

10 This inconvenience can be remedied by installing a pressure compensator in the water supply pipelines up the line from the thermostatic mixing device. However, this additional apparatus increases the size and complexity of the installation also because it must be linked to both of the cold water and hot water supply pipes; that increases the cost of the apparatuses and the installation operations; besides, it is a rather delicate operation; it is easily subject to failure, especially due to deposits, and calls for a certain degree of maintenance. Its operation is not entirely satisfactory because, when the pressure in a pipeline is reduced, the compensator reduces the passage offered to the other pipeline and thus corrects the mixing ratio but modifies the flow rate that is actually drawn. Furthermore, under certain conditions, a pressure compensator can give rise to instability phenomenon.

According to Italian Patent Application No. 99 A 000 455, a thermostatic mixing device, controlled by thin obstruction plates situated at its inlet, can be arranged so as to function correctly, both when the maximum flow rates for which it was designed are drawn and also when reduced flow rates are drawn in the water supply lines of apparatuses with high flow

- 3 -

resistance without entailing the above-mentioned inconvenience and without necessitating a pressure compensator by having the user arrange the thermostatic mixing faucet so as to adapt it to the various conditions of use or to the power supply of apparatuses that absorb flow rates that differ widely among each other.

This can be achieved by virtue of the fact that the entry passage openings of the thin blocking plates, which control the inlet pipes for the hot water and for the cold water, are shaped in relation to at least one of the pipelines for hot water and for cold water so as to present restricted passage cross-sections in a field adjacent to the occlusion position and large cross-section passage segments in the remaining regulating field.

In this way, when the thermostatic mixing faucet must supply one or several apparatuses that take a small flow rate, it is moved in its first regulation field, which takes place the moment the thermostatic mixing faucet is shifted from the occlusion position. The restricted cross-section of at least one of the entry passage openings then causes a relatively high pressure drop, although in the presence of a small flow rate caused by the high resistance at the outlet, and makes the thermostatic mixing faucet practically insensitive (to the effects of its stability) in contrast to the also significant pressure differences between the water supply pipelines. When, on the other hand, the thermostatic mixing faucet must supply apparatuses that absorb a large flow rate, it is moved into its second regulating field, which follows the first one. The large cross-section of the entry passage openings then makes it possible to draw the maximum flow rate that the

- 4 -

thermostatic mixing faucet is capable of and, under these conditions, any possible, even significant, pressure differences between the water supply pipelines will not cause any inconvenience.

5

This provision ensures the perfect operation of a thermostatic mixing faucet, but it requires a maneuver, albeit a simple one, on the part of the user, and, furthermore, it cannot be applied to thermostatic mixing devices at whose inlet thin blocking plates are not installed.

10

In view of this, the primary purpose of this invention is to provide a valve intended to be installed at the inlet of a thermostatic mixing device of any kind, which would be suitable for automatically bringing about a performance in accordance with the one that is caused by the above-mentioned provision, causing a partial division of the passage cross-section, while the thermostatic mixing device supplies an apparatus with low water flow demand, which offers high resistance against the flow and, on the other hand, leaving the water supply line substantially clear, while the thermostatic mixing device supplies one or several apparatuses with a high overall water flow demand, which, together, gives rise to a low resistance against the flow.

20

25

Another object of the invention is to provide such an automatic valve, which would furthermore combine the function of a nonreturn valve as is required in many cases in which it is installed.

30

Yet another object of the invention is to provide such a valve, which would have a simple structure, be easy to

manufacture, relatively cheap and so designed as to facilitate maintenance.

SUMMARY OF THE DISCLOSURE

5 The first object of the invention is achieved in a valve intended for installation in the inlet of a thermostatic mixing device by virtue of the fact that the valve comprises a tubular body intended to be inserted in or constitute part of
10 a pipe or connection for water supply, said body having a holding seat; a cursor that can be moved in said body with respect to said seat between a first position in which it at least partly occludes said seat, and a second position in which it leaves said seat substantially clear to permit the
15 passage of a relatively large flow rate, said cursor being subjected, on the one hand, to the pressure of the water supply pipeline and, on the other hand, to the pressure existing inside said mixing device; and a spring that works on said cursor, pushing it toward said first position, said
20 spring being dimensioned so that said cursor, with respect to said seat, will assume said first position or a position close to it under conditions in which the water flow demanded by said mixing device is relatively low, and will be shifted toward said second position or until it reaches it under
25 conditions in which the water flow demanded by said mixing device is relatively high; wherein said cursor comprises means which, when said cursor assumes said first position or a position close to it, permit the passage of a flow rate sufficient only to supply a mixing device with a relatively
30 low water flow demand.

In this way, when the water supply of an apparatus with low

- 6a -

water flow demand tends to cause inside the thermostatic mixing device the establishment of a pressure close to the water supply pressure, the small difference between these pressures causes the cursor to assume a position close to said first position or coinciding with it and leaving clear a small passage cross-section, thus causing a pressure drop because of which the pressure that is actually established inside the thermostatic mixing device is limited and cannot give rise to any instability. When, on the other hand, the supply to apparatuses having a high overall water flow demand is such that inside the thermostatic mixing device a very low pressure develops, then the cursor, pushed by a greater pressure difference, assumes a position close to the second position while coinciding with it, leaving clear a large passage cross-section, thus not causing a pressure drop that would appreciably reduce the volume of water drawn, whereas, on the other hand, under these conditions, the thermostatic mixing device does not tend to display any unstable performance. The valve thus automatically -- and independently of the kind of thermostatic mixing device involved -- brings about the same effect that can be achieved by an appropriate maneuver employed by the user according to the teaching in Italian Patent Application TO 99 A 000 455.

~~position or coinciding with it and leaving clear a small~~
passage cross-section, thus causing a pressure drop because of
which the pressure that is actually established inside the
thermostatic mixing device is limited and cannot give rise to
5 any instability. When, on the other hand, the supply to
apparatuses having a high overall absorption is such that
inside the thermostatic mixing device a very low pressure
develops, then the cursor, pushed by a greater pressure
difference, assumes a position close to the second position
10 while coinciding with it, leaving clear a large passage cross-
section, thus not causing a pressure drop that would
appreciably reduce the volume of water drawn, whereas, on the
other hand, under these conditions, the thermostatic mixing
device does not tend to display any unstable performance. The
15 valve thus automatically -- and independently of the kind of
thermostatic mixing device involved -- brings about the same
effect that can be achieved by an appropriate maneuver
employed by the user according to the teaching in Italian
~~Patent Application TO-99-A-000-455.~~

20 An automatic valve, according to the invention, can be
inserted in only one water supply pipeline or in both, but
preferably it is inserted only in the cold water supply
pipeline.

25 The second object of the invention is achieved when the cursor
in said first position occludes the seat totally. In this
case, as a matter of fact, when no water is drawn or if the
flow tends to assume a direction opposite to the normal
30 direction, the cursor, shifting into said first position,
completely occludes said seat so that the valve works like a
nonreturn valve.

- 7 -

The second object of the invention can also be achieved -- even if the cursor in said first position does not totally occlude said seat -- by inserting in the valve an element, for example, a flexible and elastic membrane arranged so as to occlude at least one passage opening, while the flow tends to assume a direction opposite to the normal direction.

The structure of the valve, according to the invention, can assume various configurations that are specifically indicated in the following description and in the subclaims. These and other features, objects and advantages of the object of this invention will appear more clearly in the following description of some embodiments, constituting nonrestrictive examples, with reference to the attached drawings.

BRIEF DESCRIPTION OF THE DRAWINGS

Reference now is made to the accompanying drawings in which:

Figure 1 is a diametrical cross-section, illustrating a first embodiment among the simplest possible ones of the valve, according to the invention, in its first position;

Figure 2 illustrates the valve, according to said first embodiment, in its second position;

Figure 3 and Figure 4 illustrate, respectively, in the first and in the second positions, a second embodiment of the valve, according to the invention;

Figure 5, Figure 6 and Figure 7 illustrate in three

- 8 -

different operating positions a third embodiment of the valve, according to the invention;

Figure 8 and Figure 9 illustrate, respectively, in the first and in the second positions, a fourth embodiment of the valve, according to the invention;

Figure 10 and Figure 11 illustrate, respectively, in the first and in the second positions, a fifth embodiment of the valve, according to the invention; and

Figure 12 and Figure 13 illustrate, respectively, in the first and in the second positions, a sixth embodiment of the valve, according to the invention.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

With reference to Figures 1 and 2, a first, very simple embodiment of the valve, according to the invention, comprises a tubular body 1 intended to be inserted in or constitute part of at least one pipeline or connection for supplying a thermostatic mixing device, a holding seat 2 presented by said body 1, and a cursor 3 that can be moved in said body 1 with respect to said seat 2 between a first position (Figure 1) in which it partially occludes said seat 2 and a second position (Figure 2) in which it substantially leaves said seat 2 clear. This cursor is obviously subjected, on the one hand, to the (higher) pressure (according to the figures) of the water supply pipeline and, on the other hand, to the pressure (which is lower, according to the figures) that is present inside the thermostatic device. Cursor 3 has one or several openings 4, which are always pervious and which are so dimensioned as to

- 9 -

allow the passage of a flow that is sufficient only to supply an apparatus with low intake, and openings 5, which are so dimensioned as to permit the passage of a large flow, which become pervious only when cursor 3 leaves its first position and moves toward the second position or reaches it. The valve furthermore comprises a spring 6 that acts on cursor 3, moving it toward the first occlusion position, and said spring 6 is so dimensioned that the pressure drop that is experienced by a small flow through openings 4 will not be sufficient to overcome the force of the spring when it is required to expose passage openings 5 so that cursor 3, with respect to seat 2, maintains a position that causes a reduced passage cross-section, that is, the cross-section of openings 4 only, under conditions involving the supply of an apparatus with low absorption. On the other hand, under conditions involving the supply of apparatuses having a high overall absorption, the pressure difference that works on cursor 3 (downward, according to the figures), overcoming the force of spring 6, shifts cursor 3 toward the second position or until it reaches it (Figure 2) and uncovers the passage openings 5. In this way, cursor 3, with respect to seat 2, assumes a position that brings about a large passage cross-section under conditions involving the supply of apparatuses having a high overall absorption, and it does not obstruct the passage of a large flow rate.

It follows from this that the valve protects the thermostatic mixing device, preventing the development of a high pressure in it when a low-absorption apparatus is supplied, while the valve does not appreciably obstruct the flow when one or several apparatuses with high overall absorption are supplied.

- 10 -

Figures 3 and 4 show how the valve, according to the preceding figures, can in a simple manner be made to work also as a nonreturn valve. In this case, a flexible and elastic membrane 7 is applied to cursor 3, corresponding to its openings 4. As long as no flow runs through the valve or if the flow tends to be inverted, membrane 7 occludes openings 4, while openings 5 are not pervious because spring 6 keeps the valve in its first position. A flow in the opposite direction is thus prevented. On the other hand, the moment an even minimal pressure difference develops at the heads of the valves in the normal direction of water supply, membrane 7 is lifted, thus clearing openings 4. This is represented in correspondence to the second position of the valve in Figure 4; but it is understood that membrane 7 is raised in the presence of a small flow also if cursor 3 remains in its first position or close to it.

The valve according to Figures 5 and 7 differs from the one according to Figures 1 and 2 only by virtue of the fact that in cursor 3, opening 4, intended to permit the passage of a reduced flow, is also located in the first position up the line from seat 2 and precisely between openings 5 that are intended to permit the passage of a strong flow and seat 2. Therefore, when cursor 3 is in its first position (Figure 5), it completely occludes seat 2: the valve thus works as a nonreturn valve. When a small pressure difference is developed at the heads of the valve, spring 6 permits only a small shift of cursor 3, which remains in the proximity of its first position (Figure 6), while only opening 4 is exposed, permitting the passage of a reduced flow and preventing the establishment of a high pressure in the thermostatic mixing device. By increasing the pressure difference at the heads of the valve, spring 6 permits a further shift of cursor 3 toward

- 11 -

its second position (Figure 7) and openings 5, which permit the passage of a large flow, are then uncovered.

The valve, according to Figures 8 and 9, works in an entirely similar fashion; here, small passage openings 4 and large passage openings 5 are replaced by openings 5' that have a shape that tapers toward seat 2, which thus assume the functions both of openings 4 and of openings 5 with a gradual increase in the pressure cross-section, along with the increase in the shift of cursor 3. The valve, thus described, also has a nonreturn function because openings 5', with their tapered shape, are entirely up the line from seat 2 when the valve is in the resting position.

The valve, according to Figures 10 and 11, operates in the same way as a valve, although it also acts as a nonreturn valve, according to Figures 3 and 4, with cursor 3 having a more elaborate structure; in this case, it is made up of several parts to ensure safe guidance in body 1 and to permit a more free passage of the flow in the second position of the valve. In this case, cursor 3 has parts 3⁰, which run against the internal surface of body 1 to guide the cursor, and it brings about a closure on seat 2 by means of a packing 8. The removal of this packing 8 from seat 2 brings about large passage cross-sections, which replace openings 5. In this case, openings 4, with which cooperates nonreturn membrane 7, can be made in a part 3' of cursor 3, which can be replaced. It thus becomes possible in the best way to adapt to the operating characteristics of the valve, both to the flow rate required by the apparatus with the lesser absorption, which is to be supplied with water, and to the pressure that normally exists in the water supply network.

- 12 -

In the embodiment, according to Figures 12 and 13, which, by the way, is similar to the embodiment, according to Figures 10 and 11, openings 4 with a small cross-section are replaced by a so-called flow rate regulator 9. A flow rate regulator is a known accessory, which is commercially available; it always permits the passage of a flow rate close to a predetermined value, regardless of the pressure that may develop at its heads (within certain limits). Therefore, this accessory replaces narrow openings 4 in the valve according to the invention and, with respect to them, offers the advantage that it does not have to be adapted to the pressure normally prevailing in the water supply network.

These flow rate regulators are commercially available also connected to a nonreturn valve (for example, according to German Patent Application No. 196 03 393) and can as such be applied in the valves, according to the invention, in cases where it is advisable to prevent an inverted flow.

It must be understood that a flow rate regulator can be employed by way of substitution of openings 4 with a small cross-section also in some of the embodiments described earlier.

As noted earlier, the automatic valve, according to the invention, can be inserted in both hot water and cold water supply pipelines or alternately in only one of them, preferably the one for the cold water, while the other water supply pipeline does not have any such valve.

The user, therefore, does not have to preset the thermostatic

- 13 -

mixing device for correct operation under conditions different from those selected by him because that job is automatically done by the valve according to the invention. In addition to making the entire operation much easier for the user, this
5 also prevents any possibility of error on the part of the user.

10 A valve intended for installation in the inlet of a thermostatic mixing device is disclosed, which comprises a tubular body intended to be inserted in a water supply pipe, a holding seat presented by said body, a cursor that can be moved in the body with respect to the seat between a first position in which it at least partly occludes the seat and a second position in which it leaves the seat substantially
15 clear, said cursor being subjected, on the one hand, to the pressure of the water supply pipeline and, on the other hand, to the pressure existing inside the thermostatic mixing device, and a spring that works on the cursor, pushing it toward the occlusion position, said spring being dimensioned
20 so that the cursor, with respect to the seat, will assume a position that brings about a reduced passage cross-section under conditions involved in the water supply of an apparatus that has a low degree of absorption and in which, with respect to the seat, it assumes a position causing a large passage
25 cross-section under conditions involved in the water supply of apparatuses featuring a total high absorption. The valve can also comprise means that act as a nonreturn valve, and it can be equipped with a flow rate regulator.

30 It must be understood that the invention is not confined to the embodiments described and illustrated by way of example. A number of modifications, in addition to those already

5 also be completed by other accessories such as, for example, a
water filtration net.

10 described and illustrated without departing from the scope and spirit of the present invention as defined by the appended claims.

THE UNIVERSITY OF CHICAGO

- 15 -

CLAIMS:

1. An automatic valve intended for installation in the inlet of a thermostatic mixing device, comprising:

5 a tubular body (1) intended to be inserted in or constitute part of a pipe or connection for water supply, said body (1) having a holding seat (2);

10 a cursor (3) that can be moved in said body (1) with respect to said seat (2) between a first position in which it at least partly occludes said seat (2), and a second position in which it leaves said seat (2) substantially clear to permit the passage of a relatively large flow rate, said cursor (3) being subjected, on the one hand, to the pressure of the water supply pipeline and, on the other hand, to the pressure
15 existing inside said mixing device; and

a spring (6) that works on said cursor (3), pushing it toward said first position, said spring (6) being dimensioned so that said cursor (3), with respect to said seat (2),

20 will assume said first position or a position close to it under conditions in which the water flow demanded by said mixing device is relatively low, and

will be shifted toward said second position or until it reaches it under conditions in which the water flow demanded by said mixing device is relatively high;

25 wherein said cursor (3) comprises means (4, 5', 9) which, when said cursor (3) assumes said first position or a position close to it, permit the passage of a flow rate sufficient only to supply a mixing device with a relatively low water flow demand.

30

2. Automatic valve according to Claim 1, wherein said cursor (3) in said first position totally occludes said seat (2) so

that the valve will also work as a nonreturn valve.

3. Automatic valve according to Claim 1, wherein an element (7) intended to act as nonreturn valve is inserted in it.

5 4. Automatic valve according to Claim 3, wherein said element (7), functioning as a nonreturn valve, consists of a flexible and elastic membrane, arranged so as to occlude at least one passage opening (4), while the flow tends to assume
10 a direction opposite to the normal direction.

15 5. Automatic valve according to one of Claims 1 to 4, wherein said cursor (3) has at least one opening (4) with small dimensions, intended to permit the passage of a flow rate sufficient only to supply a mixing device with a relatively low water flow demand.

20 6. Automatic valve according to Claim 5, wherein at least one opening (4) with small dimensions is permanently pervious.

25 7. Automatic valve according to Claim 5, wherein said opening (4) with small dimensions is situated up the line from said seat (2) when said cursor (3) assumes said first position, and becomes pervious only when said cursor (3) undergoes a minor shift toward its second position.

30 8. Automatic valve according to one of Claims 1 to 4, wherein said cursor (3) comprises openings (5) with large dimensions which are situated up the line from said seat (2) when said cursor (3) assumes said first position or a position close to it, and which become pervious when said cursor (3) shifts toward its second position or reaches it.

- 17 -

9. Automatic valve according to Claim 8, wherein said openings (5') with large dimensions have a tapered form so as to become pervious in an increasing manner, along with the increase in the shift of said cursor (3) from said first position to said second position.

10. Automatic valve according to Claim 9, wherein said openings (5') with the tapered shape are situated entirely up the line from said seat (2) when said cursor (3) assumes said first position so that the valve will also work as a nonreturn valve.

11. Automatic valve according to one of Claims 1 to 10, wherein said cursor (3) has a holding packing (8), acting in said first position with respect to said seat (2), and whose removal, when said cursor (3) is shifted toward said second position, clears wide passage cross-sections.

12. Automatic valve according to one of Claims 1 to 4, wherein a known flow rate regulator (9) is mounted in said cursor (3), whose substantially constant flow rate is adapted to the anticipated supply flow rate of a mixing device with a relatively low water flow demand.

13. Automatic valve according to Claim 12, wherein said flow rate regulator (9) is of a type provided with means that act as nonreturn valve.

14. Automatic valve according to one of the preceding claims, which is installed in both water supply pipelines of a thermostatic mixing device.

AMENDED SHEET

15. Automatic valve according to one of Claims 1 to 13, which is installed in only one of the water supply pipelines of a thermostatic mixing device.

5

16. Automatic valve according to Claim 15, which is installed in the cold water supply pipeline going to a thermostatic mixing device.

10

17. Thermostatic mixing device which is provided with at least one automatic stabilization valve according to one or several of the preceding claims.

2007-08-08 09:00:00

AMENDED SHEET

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
29 March 2001 (29.03.2001)

PCT

(10) International Publication Number
WO 01/22185 A1

(51) International Patent Classification⁷: G05D 7/01.
F16K 15/02

(21) International Application Number: PCT/EP00/07353

(22) International Filing Date: 29 July 2000 (29.07.2000)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
TO99A000802 21 September 1999 (21.09.1999) IT

(71) Applicant (for all designated States except US): MASCO
CORPORATION OF INDIANA [US/US]; 55 East 111th
Street, Indianapolis, IN 46280 (US).

(72) Inventor; and

(75) Inventor/Applicant (for US only): KNAPP, Alfons
[DE/DE]; Klockstrasse 15, D-88400 Biberach (DE).

(74) Agents: OPPERMAN, Ewald et al.; Oppermann & Op-
permann, Am Wiesengrund 35, D-63075 Offenbach (DE).

(81) Designated States (national): AE, AG, AL, AM, AT, AU,
AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CR, CU, CZ,
DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR,
HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR,
LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ,
NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM,
TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.


(84) Designated States (regional): ARIPO patent (GH, GM,
KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian
patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European
patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE,
IT, LU, MC, NL, PT, SE), OAPI patent (BF, BJ, CF, CG,
CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

Published:

— With international search report.

For two-letter codes and other abbreviations, refer to the "Guid-
ance Notes on Codes and Abbreviations" appearing at the begin-
ning of each regular issue of the PCT Gazette.

(54) Title: AUTOMATIC VALVE FOR THE STABILIZATION OF A THERMOSTATIC MIXING DEVICE



(57) Abstract: A valve intended for installation in the inlet of a thermostatic mixing device comprises a tubular body (1) intended to be inserted in a water supply pipe, a holding seat (2) presented by the body (1), and a cursor (3) that can be moved in the body (1) with respect to the seat (2) between a first position (Figure 12) in which it at least partly occludes the seat (2) and a second position (Figure 13) in which it leaves the seat (2) substantially clear. The cursor (3) is subjected, on the one hand, to the pressure of the water supply pipeline and, on the other hand, to the pressure existing inside the thermostatic mixing device. The valve further comprises a spring (6) that works on the cursor (3), pushing it toward the occlusion position. The valve can also comprise means that act as a non-return valve, and it can be equipped with a flow rate regulator (9).

WO 01/22185 A1

10/088700

1/4




Fig-1




Fig-3




Fig-2




Fig-4

00/088700

2/4




Fig-5




Fig-6




Fig-7

10'088700

3/4




Fig-8




Fig-9

4/4

10/088700




Fig-10




Fig-12




Fig-11




Fig-13

Docket No.

145-3065-U

Declaration and Power of Attorney For Patent Application

English Language Declaration

As a below named inventor, I hereby declare that:

My residence, post office address and citizenship are as stated below next to my name,

I believe I am the original, first and sole inventor (if only one name is listed below) or an original, first and joint inventor (if plural names are listed below) of the subject matter which is claimed and for which a patent is sought on the invention entitled

AUTOMATIC VALVE FOR THE STABILIZATION OF A THERMOSTATIC MIXING DEVICE

the specification of which

(check one)

☒ is attached hereto.

☐ was filed on _____ as United States Application No. or PCT International Application Number _____

and was amended on _____

(if applicable)

I hereby state that I have reviewed and understand the contents of the above identified specification, including the claims, as amended by any amendment referred to above.

I acknowledge the duty to disclose to the United States Patent and Trademark Office all information known to me to be material to patentability as defined in Title 37, Code of Federal Regulations, Section 1.56.

I hereby claim foreign priority benefits under Title 35, United States Code, Section 119(a)-(d) or Section 365(b) of any foreign application(s) for patent or inventor's certificate, or Section 365(a) of any PCT International application which designated at least one country other than the United States, listed below and have also identified below, by checking the box, any foreign application for patent or inventor's certificate or PCT International application having a filing date before that of the application on which priority is claimed.

Prior Foreign Application(s)

Priority Not Claimed

PCT/EP00/07353

PCT

29/07/2000

☐

(Number)

(Country)

(Day/Month/Year Filed)

TO99A000802

Italy

21/09/1999

☐

(Number)

(Country)

(Day/Month/Year Filed)

(Number)

(Country)

(Day/Month/Year Filed)

☐

I hereby claim the benefit under 35 U.S.C. Section 119(e) of any United States provisional application(s) listed below:

(Application Serial No.)

(Filing Date)

(Application Serial No.)

(Filing Date)

(Application Serial No.)

(Filing Date)

I hereby claim the benefit under 35 U. S. C. Section 120 of any United States application(s), or Section 365(c) of any PCT International application designating the United States, listed below and, insofar as the subject matter of each of the claims of this application is not disclosed in the prior United States or PCT International application in the manner provided by the first paragraph of 35 U.S.C. Section 112, I acknowledge the duty to disclose to the United States Patent and Trademark Office all information known to me to be material to patentability as defined in Title 37, C. F. R., Section 1.56 which became available between the filing date of the prior application and the national or PCT International filing date of this application:

(Application Serial No.)

(Filing Date)

(Status)
(patented, pending, abandoned)

(Application Serial No.)

(Filing Date)

(Status)
(patented, pending, abandoned)

(Application Serial No.)

(Filing Date)

(Status)
(patented, pending, abandoned)

I hereby declare that all statements made herein of my own knowledge are true and that all statements made on information and belief are believed to be true; and further that these statements were made with the knowledge that willful false statements and the like so made are punishable by fine or imprisonment, or both, under Section 1001 of Title 18 of the United States Code and that such willful false statements may jeopardize the validity of the application or any patent issued thereon.

POWER OF ATTORNEY: As a named inventor, I hereby appoint the following attorney(s) and/or agent(s) to prosecute this application and transact all business in the Patent and Trademark Office connected therewith. *(list name and registration number)*

Kwadjo Adusei-Poku, Registration No. 39,892

Edgar A. Zarins, Registration No. 30,986

Leon E. Redman, Registration No. 26,021

Myron B. Kapustij, Registration No. 26,748

Lloyd D. Doigan, Registration No. 30,170

Send Correspondence to: Kwadjo Adusei-Poku
Masco Corporation
21001 Van Born Road
Taylor, Michigan 48180

Direct Telephone Calls to: *(name and telephone number)*

Kwadjo Adusei-Poku (313) 792-6432

Full name of sole or first inventor

ALFONS KNAPP

Sole or first inventor's signature

Residence

Klockstrasse 15, D-88400 Biberach/Riss, Germany

Citizenship

Germany

Post Office Address

Date

18 MAR 2 2002

DEX

Full name of second inventor, if any

Second inventor's signature

Date

Residence

Citizenship

Post Office Address